NOTICE INVITING QUOTATION

Name of the Work: Supply, Installation, Testing and Commissioning of Internal Electrification work for newly set up Research Labs in Academic Block, Permanent Campus, IISER Berhampur.

NIQ NO - IISERBPR/IWD/NIQ/2026-27/35 dated 26/10/2026

(Last date of NIQ submission up to 1500 Hrs. on 02/11/2026)

INSTITUTE WORKS DEPARTMENT

IISER BERHAMPUR

Permanent Campus, At/Po- Laudigam, Dist.- Ganjam ,
Odisha, India-760003

Signature of Bidder with Seal

INDEX

Name of the work: Supply, Installation, Testing and Commissioning of Internal Electrification work for newly set up ten (10) Research Labs in Academic Block, Permanent Campus, IISER Berhampur.

Sl. No.	Particulars	Pages
	NIQ Document	
1.	Index	02
2.	NIQ Information to Bidders	03
3.	Qualification, eligibility criteria & information for Bidders	04
4.	Schedules	05-07
5.	Structure & Organization	08
6.	Application form for fund transfer through RTGS / NEFT	09
7.	Approved Make list	10
8.	Terms & Conditions	11
9	Financial Bid (Annexure-A)	12-14

Sr. Executive Engineer (E)
For and on behalf of the Director, IISER Berhampur

Signature of Bidder with Seal

NIQ No - IISERBPR/IWD/NIQ/2026-27/35 dated 26/10/2026

The Sr. Executive Engineer (Electrical), IISER Berhampur on behalf the Director, IISER Berhampur invites Percentage rate quotations in sealed envelope from the interested eligible bidders having valid electrical licenses (MV or above) who had carried out similar nature of works. The details of Schedule of Quantity attached at **annexure A.**

Notice Inviting Quotation

- Last date of submission of Quotation in **Tender box** kept at near **Security Post, Ground Floor, Academic Block, Permanent Campus, IISER Berhampur** up to **15:00 Hrs**. on **02/11/2026.**
- The Quotations shall be opened on **02/11/2026** at **15:30 Hrs**. at Board Room, 1st Floor, Academic Block, Permanent Campus, IISER, Berhampur.
- **Name of work:** Supply, Installation, Testing and Commissioning of Internal Electrification work for newly set up ten (10) Research Labs in Academic Block, Permanent Campus, IISER Berhampur.
- Estimated Cost: **Rs.3,86,006/-**
- EMD: **Rs. 7,720/-**
- Duration of Work: 30 Days
- EMD to be deposited in favor of "The Director, IISER, Berhampur".
- EMD should be in the form of bank transfer (I-Collect) / Bank draft in favor of The Director, IISER Berhampur payable at the main branch of SBI, Berhampur only. Bidders may visit, if any assistance required **http://www.iiserbpr.ac.in**. No interest shall be paid on the EMD deposited. The bidder is also required to submit the bank details in the RTGS IISER Berhampur format available on this link http://www.iiserbpr.ac.in/pdf-_doc/RTGS%20NEFT%20Form_IISER%20Berhampur.docx for getting the refund of EMD/Payment.
- Help Desk – 0680-2227727/7724, email: - iwd@iiserbpr.ac.in
- For details visit www.iiserbpr.ac.in

Signature of Bidder with Seal

Qualification, Eligibility Criteria & Information for Bidders: -

1. The bidder should have average annual financial turnover (Gross) of at least Rs. 2 Lakh during the immediate last three consecutive years, as per their balance sheet ending 31.03.2026.
2. The bidder should have Valid Electrical License (MV or Above) and Proof of having similar work experience (Similar work means: The bidder should have done electrical wiring/ cable works etc.)
3. The Bidders must submit documentary evidence in support of the above claims and similar works in the form of certified copy of work order or completion certificate or payment certificate for the executed work.
4. List of document to be submitted by the contractor are as indicated below.

Sl. No.	Description
1.	Acknowledgement of EMD deposited by bank transfer (SBI I-Collect). Bidders may visit, if any assistance required: https://www.onlinesbi.com/sbicollect/icollecthome.htm
2.	Copy of Valid Electrical License (MV or Above)
3.	Structure & Organization (Annexure-I).
4.	Application Form for Fund Transfer through RTGS / NEFT.
5.	Copy of Certificate of Registration for GST.

This NIQ can also be seen on Institute website www.iiserbpr.ac.in .

Signature of Bidder with Seal

SCHEDULES

SCHEDULE 'A'

Schedule of quantities (enclosed as Annexure – A)

SCHEDULE 'B'

Schedule of materials to be issued to the contractor: -

Sl. No	Description of Item	Quantity	Rate	Place of Issue
-As specifically mentioned in schedule of quantities (if any)-				

SCHEDULE 'C'

Tools and plants to be hired to the contractor

Sl. No	Description	Hire charges per day	Place of Issue
1	**2**	**3**	**4**
--Nil--			

SCHEDULE 'D'

Extra schedule for specific requirements / documents for the work, if any. : **Nil**

SCHEDULE 'E'

Reference to General Conditions of Contract for CPWD works 2014 with amendments issued up to last date of submission of bids.

Name of the work : Supply, Installation, Testing and Commissioning of Internal Electrification work for newly set up ten (10) Research Labs in Academic Block, Permanent Campus, IISER Berhampur.

Estimated cost of work : **Rs. 3,86,006/-**

Earnest Money : **Rs. 7,720/-**
(To be return for unsuccessful bidder)

Performance Bank Guarantee : NA

SCHEDULE 'F'
General Rules & Directions:

Office Inviting Quotation : **Institute Works Department, IISER Berhampur**

Maximum percentage for quantity of items of work to be executed beyond which rates are to be determined in accordance with clauses 12.2 & 12.3. **30%**

Definitions :

2 (v) Engineer-in-charge : Sr. EE(E), IWD, IISER Berhampur

2(viii) Accepting Authority : Director, IISER Berhampur

2(x) Percentage on cost of material and labour to cover all overheads and profits : 15%

Signature of Bidder with Seal

2(xi)	Standard Schedule of Rates	:	Market Rates/DSR-2025
2(xii)	Department	:	**Institute Works Department, IISER Berhampur.**
9(i)	Standard CPWD Contract Form	:	**NA**

Clause 1:

(i)	Time allowed for submission of performance, program chart (Time & Progress) and applicable labor licenses, registration with EPFO, ESIC and BCOQ Welfare Board or proof of applying thereof from the date of issue of letter of acceptance.	**NA**
(ii)	Maximum allowable extension with late fee @ 0.1% per day of Performance Guarantee beyond the period provided in	
	Above :	**NA**

Clause 2:

	Authority for fixing compensation under Clause-2	: **Director, IISER Berhampur**

Clause 2A:

	Whether Clause 2A shall be applicable	: **Not Applicable**

Clause 5:

	Number of days from the date of issue of letter of acceptance for reckoning date of start	**7 Days**

Clause 11:

	Specifications to be followed for execution of work	CPWD Specification and the specification given in the BOQ and as per layout drawing

Clause 12:

Type of work:

12.2 and 12.3	Deviation limit beyond which clauses 12.2 & 12.3 shall apply for this work	**30%**

Clause 16:

a. Competent Authority for deciding reduced rates	.: Director, IISER Berhampur
b. Extension of Time up to 30% of contract duration	SE, IWD
c. Extension of Time above 30% of contract duration	The Director, IISER Berhampur

Signature of Bidder with Seal

Clause 18:

List of Mandatory machinery, tools and plants to be deployed by the contractor at site. **: As required.**

Note: The list of machinery, tools & plants to be deployed by the contractor at site are minimum. The contractor shall deploy additional machinery, tool & plants in order to maintain the progress of the work without any extra cost to the department.

Clause 25:

(i)	Constitution of Dispute Redressal Committee (DRC)	Competent Authority to appoint DRC and Arbitrator
	DRC shall consist of one Chairman and two members.	Director, IISER Berhampur
(ii)	Place of Arbitration	Berhampur

Signature of Bidder with Seal

Structure & Organization

1.	Name and address of Bidder	
2.	Telephone No. / Fax No. / email address	
3.	Legal status of the bidder The applicant is: a) An individual b) A proprietary firm c) A Firm in partnership d) A limited company or corporation	
4.	Particulars of registration with various Govt. bodies (Attach attested photocopies) a) Registration Number b) Organization / Place of registration c) Date of validity	
5.	Has the bidder or any constituent partner in case of partnership firm Limited Company/Joint Venture, ever been convicted by the court of law? If so, give details.	
6.	Any other information considered necessary but not included necessary but not included above.	

Signature of Bidder(s) with Seal

Signature of Bidder with Seal

State Bank of India, Main Branch, Berhampur, Ganjam	Indian Institute of Science Education and Research Berhampur

Application Form for Fund Transfer through RTGS / NEFT **Date:**

Counterfoil

SBI, Main Branch, Berhampur

Received from **IISER Berhampur** By

Cheque / Transfer for RTGS on **Bank**

Favoring (beneficiary name)

Beneficiary Bank A/c No

Amount **Rs.**

Bank's Charges Rs.....

Total Rs.....

Cheque No.	
Date	
Amount	

Application for RTGS Remittance

SBI Main Branch,
Berhampur, Branch Code:
000033
Remitter Name: **IISER Berhampur**

Please Remit the sum of Rs.
(Rupees_____
only**)**

As per details below by debiting our Account No:**35821019850** For the total amount including charges applicable (if any)

Name of the beneficiary	
Bank's name	
Branch	
IFSC Code	
Account No.	
MICR Code	
Type of Account	

Amount Rs	
Amount in Words Rs	
Bank Charges Rs	
Total Rs.	

(Authorized Signatory - 1)
(Authorized Signatory - 2)

Address : Finance & Accounts, IISER Berhampur
Tel No. : 0680-222 7708

Prepared and Checked by payee		**Forwarded By (Concerned Department / Section)**	
Signature of authorized signatory		Signature	
Name		Name	
Designation		Designation	
Firm / Agency Name :		Department	

***Please affix a rubber stamp**

Date of Transfer	
Amount Rs	
Transaction / UTR No.	

Signature of Bidder with Seal

Approved Make List

Sl. No	Description of Items	Approved Make
1	FRLS PVC Insulated Copper Wire	Polycab, RR Cables, Havells
2	Power Cables / Control Cables up to 11 KV	Havells, Polycab, Finolex
3	Medium Class PVS Conduit and Accessories	AKG, BEC, PRECISION
4	GI Modular Box	Legrand , Schneider Electric , L&T
5	Modular Switch and Socket	Legrand , Schneider Electric , L&T
6	MCB, MCB DB, Enclosure Box	Legrand , SIEMENS, L&T
7	Industrial Power Socket	Legrand, Schneider Electric, ABB,
8	MS Cable tray	RMCON, BEC, STEEL CRAFT or Equivalent
9	Copper Earthing Material	ISI approved make

Terms and Conditions: -

1. The bidder shall submit quote in single envelope.
2. The work should be completed in **30 days** from the date of award of work.
3. The EMD is liable to be forfeited in full if the bidders fail to start the work after award or on withdrawal of offer before award of the work.
4. The Bidder should have valid **GST registration number.**
5. The rates shall be inclusive of all taxes, transportation & any other charges/arrangement of electricity/water etc. and apply to all heights; floors, leads and nothing extra shall be paid.
6. The Contractor / Bidder / Party have to **submit GST invoice** for payment of each running or final bill with proper abstract and MB as per the agreed rate in the Schedule of Rate.
7. The department shall not be responsible for any accident and theft before handing over and completion of work.
8. The department can close the work order at any time without any notice.
9. Security Deposit shall be deducted @2.5% of the gross amount of each running & final bill. The Security Deposit shall not be refunded before the expiry of 6 months after the issue of the work completion certificate or from the date of the final bill has been prepared and passed, whichever is later.
10. Any damage/mishappenings/legal proceeding/ compensation occurred during the execution of the contract shall be borne by the agency and department shall not be responsible for any such occurrence.
11. Statutory recoveries/deduction such as TDS on income Tax and Labor Cess as applicable shall be made from the Payments/bills.
12. The contractor has to make own arrangement of all safety appliances, scaffolding T&P etc. required to complete the work.
13. The work shall be executed as per CPWD specifications 2013 (Vol.-I & II) & GCC-2014 with up to date amendments.
14. **LD:** In case of delay from the contractor, a maximum amount of 5% of awarded value not by way of penalty, @1.0% per week of delay shall be recovered from the agency.
15. No advance payment will be paid, Payment will be made after completion and charging of the work.
16. TDS & applicable GST shall be affected as the bill. 1% Labour Cess shall be recovered from the bills. The bidders should quote be considering this.
17. **Enclosed: Schedule of Quantities:** (Annexure – A)

Sr. Executive Engineer(E)
For and on behalf of the Director, IISER Berhampur

Annexure-A

NIQ NO - IISERBPR/IWD/NIQ/2026-27/35 dated 26/ 10/2026

Schedule of Quantities/Price-Bid

Name of the work: Supply, Installation, Testing and Commissioning of Internal Electrification work for newly set up ten (10) Research Labs in Academic Block, Permanent Campus, IISER Berhampur.

BOQ Sl. No	Description	Qty	Unit	Rate/Unit (Including all taxes & Levis) (in Rs.)	Amount (Including all taxes & Levis) (in Rs.)
1	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS/HFFR PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.				
(i)	2 X 10 sq. mm + 1 X 6 sq. mm earth wire	Meter	85	621.00	52,785.00
(ii)	4 X 10 sq. mm + 2 X 6 sq. mm earth wire	Meter	65	1,253.00	81,445.00
2	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
(i)	Double pole-63Amp	Each	3	980.00	2,940.00
(ii)	Single pole-63 Ampere	Each	2	430.00	860.00
(iii)	Triple pole-32Amp	Each	1	1,070.00	1,070.00
3	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
	Triple Pole- 32 Ampere	Each	6	1,070.00	6,420.00
4	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, Ics =100% Icu and Operational Voltage 690V etc. as required.				
	125 A, 36 KA, FPMCCB	Each	3	8,644.00	25,932.00
5	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar,				

	interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).				
	4 way (4 + 12), Double door	Each	4	4,377.00	17,508.00
6	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 Volt on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator				
	8 way , Double door	Each	1	2,773.00	2,773.00
7	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required.	Meter	7	1,246.00	8,722.00
8	Providing and fixing 25 mm X 5 mm copper strip in 40 mm dia G.I. pipe from earth electrode including connection with brass nut, bolt, spring, washer excavation and re-filling etc. as required.	Meter	20	1,638.00	32,760.00
9	Supplying of 3.5 Core 35 Sq.mm XLPE ARMOURED Cables with ALUMINIUM Conductor 650/1100 V. grade confirming to IS : 7098 (Part-1) 1988	Meter	65	739.00	48,035.00
10	Supplying and Fixing of Four pole metal type enclosure as per as per IEC 61439-3 along with required materials for housing of MCB	Each	5	1,045.00	5,225.00
12	Supplying and Fixing of Four pole metal type enclosure as per as per IEC 61439-3 along with required materials for housing of 4 pole 125 Ampere MCCB	Each	1	2,424.00	2,424.00
13	Supplying and Drawing of Single Core 35 sq.mm FRLS Copper conductor PVC insulated as per IS-694-2010 along with required materials.	Meter	20	1,242.42	24,848.40
14	Supplying of 4 Core16 Sq.mm XLPE ARMOURED Cables with ALUMINIUM Conductor 650/1100 V. grade confirming to IS : 7098 (Part-1) 1988	Meter	65	439.00	28,535.00
15	Extended Rotary Handle for 125 Ampere MCCB housed in Cubicle panel along with required materials.	Each	1	1,818.00	1,818.00
16	Supplying and fixing following modular switch /socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
(i)	5/6 A switch	Each	52	121.00	6,292.00
(ii)	3 pin 5/6 A socket outlet	Each	52	136.00	7,072.00
17	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).				
	6 way (4 + 18), Double door	Each	1	5,299.00	5,299.00

18	Supplying and fixing 32 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top along with 32 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required	Each	1	3,355.00	3,355.00
19	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).				
	12 way (8+36), TPN, MCB DB, double door, horizontal type	Each	1	18,019.00	18,019.00
20	Supplying and installation following size of perforated painted with powder coating M.S. cable trays with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with two numbers MS/GI Suspenders i/c base of suitable size MS/GI angle, bolts & nuts, painting suspenders, fastener etc. as required.				
	100 mm width X 50 mm depth X 1.6 mm thickness	Meter	3	623.00	1,869.00
Total Amount including all Taxes					**3,86,006.00**
Bidder to quote in percentage (above/below) Estimated Cost in Rs. (_____%)					
Total Amount					
Total Amount in words: Rupees_____ only					

Note:

1. I have certified that proof of similar work experience certificate, Ref._____dated _____is attached.
2. MV License No_____is attached.
3. GST Registration No_____is attached.
4. EMD Amount deposited, Receipt No _____is attached.

Signature of Bidder(s) with Seal